

Saginaw Bay Water Intake System & Water Intake Piping



REFERENCES:

OWNER:

Village of Caseville
6767 Main Street
Caseville, MI 48725
Contact: David Quinn
(989) 963-0124 cell

ENGINEER:

Wolverine Engineers & Surveyors
312 North Street
Mason, MI 48854
Contact: Don Heck
(517) 676-9200

PRIME CONTRACTOR:

Great Lakes Dock & Materials, L.L.C.
559 E. Western Ave.
Muskegon, MI 49442
(231) 728-4172 office
(231) 728-4173 fax

CONTRACT DETAILS

CONTRACT VALUE:

\$2,566,000

CONTRACT COMPLETION DATE:

December 2006

SCOPE OF WORK:

- Built a 280'x280' Water Infiltration Bed
- 20,000 CY Mechanical Dredging
- Land portion (SUB) Jackson-Merkey Contractors
- Installed 4,300 Tons of Sand
- Installed 20,700 Tons of Gravel
- Installed 4,320 LF of 8" PVC Pipe
- Installed 2,300 LF of 16" PVC Pipe

Great Lakes Dock & Materials installed a new water intake for the Village of Caseville in Saginaw Bay. Jackson-Merkey Contractors worked as a subcontractor to install the onshore and near shore piping.